

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Detailed Estimate for the : Drilling of New Borewell and Instalng pump, motor and Providing Pipeline in ward no. 06 Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in unconsolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc	Each BW	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Forty Six Paise Only
2	100.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc 0 to 50 m	Rmtr	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
3	100.00	50 to 100 m		412.00	Rupees Four Hundred Twelve Only
4	100.00	100 to 150 m	Rmtr	458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
5	100.00	150 to 200 m	Rmtr	484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
6	100.00	200 to 250 m	Rmtr	560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
7	100.00	250 to 300 m	Rmtr	600.49	Rupees Six Hundred and Forty Nine Paise Only
8	40.00	300 to 320 m	Rmtr	622.00	Rupees Six Hundred Twenty Two Only
9	112.00	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/strips in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes)	Rmtr	1364.75	Rupees One Thousand Three Hundred Sixty Four and Seventy Five Paise Only
10	20.00	Providing and fixing 250mm dia PVC pipe and as per specification and directions.	Rmtr	1133.00	Rupees One Thousand One Hundred Thirty Three Only
11	2	175 mm dia M.S. Casing cap	Each	103.00	Rupees One Hundred Three Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
12	18	M.S. Casing pipe collars 'C' Class	Each	154.50	Rupees One Hundred Fifty Four and Fifty Paise Only
13	2	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to	No	74730.00	Rupees Seventy Four Thousand Seven Hundred Thirty Only
14	600.00	Providing, laying & jointing GI pipes conforming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc., complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe	Rmtr	340.26	Rupees Three Hundred Forty and Twenty Six Paise Only
15	100.00	Providing & fixing heavy duty collar		159.00	Rupees One Hundred Fifty Nine Only
16	1220.00	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia	Mtr	188.70	Rupees One Hundred Eighty Eight and Seventy Paise Only
17	2.00	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc., completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No.	14800.00	Rupees Fourteen Thousand Eight Hundred Only
18	44000.00	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sq cm	Sqm	0.34	and Thirty Four Paise Only
19	2.00	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's	690.00	Rupees Six Hundred Ninety Only
20	6.00	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve.	No's	1282.60	Rupees One Thousand Two Hundred Eighty Two and Sixty Paise Only
21	6.00	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia	No's	1749.00	Rupees One Thousand Seven Hundred Forty Nine Only
22	6.00	Providing and fixing of 50mm GI bend to motor GI FITTINGS TABLE)	No's	232.14	Rupees Two Hundred Thirty Two and Fourteen Paise Only
23	6.00	Providing and fixing of 50mm GI Nipple to motor . GI FITTINGS TABLE)	No's	110.56	Rupees One Hundred Ten and Fifty Six Paise Only
24	6.00	Providing and fixing of 50mm GI union to the motor (GI FITTINGS TABLE)	No's	237.12	Rupees Two Hundred Thirty Seven and Twelve Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
25	2.00	Labour Charges for end connection (MR)	No's	400.00	Rupees Four Hundred Only
26	90.00	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m)	Per length	90.64	Rupees Ninety and Sixty Four Paise Only
27	2.00	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc., Complete for basement out door type. (MR)	No's	475.00	Rupees Four Hundred Seventy Five Only
28	2.00	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP	No's	906.40	Rupees Nine Hundred Six and Forty Paise Only
29	6.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete....	No.	150.00	Rupees One Hundred Fifty Only
30	70.00	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated sheathed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554)	Mtr	169.95	Rupees One Hundred Sixty Nine and Ninety Five Paise Only
31	70.00	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc., Complete sutting road surfaces	Mtr	56.65	Rupees Fifty Six and Sixty Five Paise Only
32	6.00	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	294.58	Rupees Two Hundred Ninety Four and Fifty Eight Paise Only
33	2.00	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm around the pipe to complete depth the connections from the pipe to the conduit etc., is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia bolts, nuts washers and checknuts etc., the pipe shall have 16 through holes of 122mm dia	No's	1699.50	Rupees One Thousand Six Hundred Ninety Nine and Fifty Paise Only
34	2.00	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,	No's	271.92	Rupees Two Hundred Seventy One and Ninety Two Paise Only
35	2.00	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. (MR)	No's	1350.00	Rupees One Thousand Three Hundred Fifty Only
36	6.00	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc., Complete. 50mm dia	No's	1515.80	Rupees One Thousand Five Hundred Fifteen and Eighty Paise Only
37	2.00	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	No's	311.58	Rupees Three Hundred Eleven and Fifty Eight Paise Only
38	625.50	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications	Cum	222.38	Rupees Two Hundred Twenty Two and Thirty Eight Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
39	1390.00	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm ² including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe around to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete	Mtr	409.46	Rupees Four Hundred Nine and Forty Six Paise Only
40	625.50	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications	Cum	89.42	Rupees Eighty Nine and Forty Two Paise Only
41	2.00	BESCOM Deposits Charges	Ls	14500.00	Rupees Fourteen Thousand Five Hundred Only

[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
20/02

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

[Signature]
Chief Engineer
Yelahanka Zone
Bhoth Bangalore Mahanagara
Bangalore 92